

STATE OF OREGON INVENTORY
OF HISTORIC PROPERTIES
State Historic Preservation Office
Oregon State Parks, Salem, OR 97310



County Linn
Ranking _____
Name
(Common) Unknown
(Historic) Unknown
Address 625 East Grant Street
Present Owner Joan M. Brunson
Address 625 East Grant Street
Original Use residence
Date of Construction c. 1890
Map Reference Number 134

Physical description of property and statement of historical significance:

This is a two-story Queen Anne house with a rectangular plan. The roof in front ends with a jerkin-head while the others are gabled. The structure is clad with shiplap siding, corner boards that have capitals, trim located below the windows and shingles in the gable ends and in a band between floors. The front gable end at the second floor contains a rectangular bay. The window here contains stained glass in the upper sash and a single light in the lower sash. There is a pair of brackets below the bay and a three/one, double-hung window at the first floor.

On the left side of the west elevation there is a balcony set into the roof that is sheltered by a gable roof like a dormer. In its gable end there is a wooden arch which rests on turned posts. At the peak there are decorative brackets and bullnose decorations below. Below the balcony the first floor is clad with modern vertical siding and features a square, single-light fixed window. In the center of the elevation there is a full height rectangular bay which contains a one/one, double-hung window in the gable end and a pair below with stained glass in the upper sashes. The porch on the right has turned posts, a hip roof, a door with a single light, and a two-light casement window at the corner.

(continued)

Recorded by Heritage Investment Corporation, 813 SW Alder, Portland, OR 97204 (228-0272)
Allen, McMath-Hawkins, Architects, 213 SW Ash, Portland, OR 97204 (228-5154)

Initials _____ Date _____

Sources consulted:

625 East Grant
Map Reference Number: 134

The east elevation has a full height bay in the center containing a one/one, double-hung window in the gable end and a pair below. The porch at the right, with turned posts and a shed roof, contains a door and double-hung window. There is a wall built of horizontal siding along the street side. The small addition on the rear has a shed roof and the center interior chimney has its corbeled brick cap removed.

This house is reported to have been used as a church with a bell located in the gable roof balcony on the west elevation.

4/1/50

