



**NOTES:**

1. SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2.0%. WHEN ADJOINING LOT IS BELOW THE TOP OF CURB AND SLOPES AWAY FROM THE CURB, A NEGATIVE (AWAY FROM STREET) 2.0% SLOPE MAY BE REQUIRED.
2. SIDEWALK NOMINAL DEPTH IS 4.0"; P.C.C. SHALL HAVE A 28 DAY COMPRESSIVE STRENGTH OF 3000 P.S.I.
3. UNDER NO CIRCUMSTANCES SHALL SIDEWALK WIDTHS BE LESS THAN 5.0' WIDE FOR MORE THAN 200 LINEAL FEET.
4. EXPANSION JOINTS (FULL DEPTH) WITH PRE-MOLDED FILLER SHALL BE INSTALLED BETWEEN DRIVEWAYS AND SIDEWALKS AND AROUND ALL SIDEWALK OBSTRUCTIONS (SEE SUPP. DWGS. 00700-07 & 00700-08).
5. ISOLATION JOINTS (FULL DEPTH) SHALL BE INSTALLED BETWEEN BACK OF CURB AND FRONT OF SIDEWALK.
6. CONTRACTION JOINTS (½ DEPTH OF CONCRETE) SHALL BE INSTALLED AT APX. 15' INTERVALS.
7. TOOLED JOINTS (¾" DEPTH) SHALL BE INSTALLED AT APX. 5' INTERVALS IN WET CONCRETE WITH A JOINTER TOOL (SEE SUPP. DWG. 00600-02). TOOLED JOINTS SHALL MATCH CURB CONTRACTION JOINTS WHERE APPLICABLE. SIDEWALKS 8' AND WIDER SHALL HAVE A LONGITUDINAL TOOLED JOINT AT MIDPOINT.
8. WEEP HOLES AND PIPING SHALL EXTEND TO BACK OF SIDEWALK AND REQUIRE A COUPLER AT TERMINATION.
9. SIDEWALK SECTIONS MUST BE REPLACED AS FULL PANELS. PARTIAL REMOVAL OF PANELS IS PROHIBITED.



**CITY of LEBANON SUPPLEMENTAL DRAWING**

APPROVED

CITY ENGINEER

*Daniel J. Hauman*

**STANDARD P.C.C.  
SIDEWALK DETAILS**

DATE:

Jan. 2009

DRAWING NO:

00700-05